BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Improvements road and drains surrounding area in Ward No. 05

Agency:-m/s KRIDL

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	981	KSRRB 300-1. **Earthwork excavation** by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete asper specifications.MORTH / Chapter 3(I No-19.1, P No-133)	Cum	180.48	Rupees One Hundred Eighty And Paise Forty Eight Only
2	163.35	KSRB 4-1.2 : Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms^thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2.(P.No-12,I No-4.2)	Cum	5937.12	Rupees Five Thousand Nine Hundred Thirty Seven And Paise Twelve Only
3	376.16	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mmand down size graded granite metal coarse aggregates @0.0.69cum and fine aggregtes @ 0.460cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6(I No-4.11,P No-13)	Cum	7072.54	Rupees Seven Thousand Seventy Two And Paise Fifty Four Only
4	2275.20	KSRB 4-6.4 : Providing and removing **centering, shuttering, strutting,** propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2	Sqm	344.74	Rupees Three Hundred Forty Four And Paise Seventy Four Only

5/3/18

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of m/s KRIDL		
			Unit	Rate in Figures	Rate in Words
5	22.69	KSRB 4.9.2 : Providing **T.M.T steel reinforcement** for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3(I No-4.46.2,P No-17)	Tn	71310.20	Rupees Seventy One Thousand Three Hundred Ten And Paise Twenty Only
6	594.00	Providing and Fixing **pre cast covering Slab** made out of CC 1:2:4 with 100mm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2100.00	Rupees Two Thousand One Hundred Only
7	172.80	Providing and Fixing **pre cast covering Slab** made out of CC 1:2:4 with 250mm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	5111.00	Rupees Five Thousand One Hundred Eleven Only
8	1533.00	Providing and fixing pre cast solid cement **concrete kerb stones** made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete (P.No-25, I No-5.30)	Nos	368.28	Rupees Three Hundred Sixty Eight And Paise Twenty Eight Only
9	276.00	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 (P.No-183, I No-24.1)	Sqm	70.60	Rupees Seventy And Paise Sixty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

13/18

Contractor

Executive Engineer
Project Division
Yelahanka Zone